



Plan on Artificial Recharge to Groundwater and Water Conservation in Vellichandai Firka, Palacode Taluk, Dharmapuri District,

Tamil Nadu







By

Central Ground Water Board South Eastern Coastal Region Rajaji Bhawan, Besant Nagar Chennai

Content

S. No.

TOPIC

At a Glance

- 1 Introduction
- 2 Objectives
- 3. Study area details
 - 3.1 Location
 - 3.2 Geomorphological Setup
 - 3.3 Landuse and Soil
 - 3.4 Drainage
 - 3.5 Rainfall
 - 3.6 Hydrogeology
 - 3.7 Dynamic Ground water Resources
- 4 Spatial data integration/ conservation
- 5 Planning for recharge
 - 5.1 Justification of the artificial recharge
 - 5.2 Availability of surplus surface water for artificial recharge or conservation
 - 5.3 Proposed interventions including tentative location of artificial recharge structures and

water conservation

- 5.3.1 Artificial recharge
- 5.3.1.1 Check Dam /Nala Bund
- 5.3.1.2 Recharge shaft
- 5.3.1.3. Revival , repair of water bodies
- 5.3.2. Water Conservation Measure
- 5.3.2.1 Farm Pond
- 5.3.2.2 Micro irrigation system
- 6. Tentative Cost Estimation
- 7. Implication modalities
 - a) Time schedule
 - b) Operation and Maintenance

Name of FirkaVellichandaiTalukPalacodeDistrictDharmapuriStateTamil NaduTotal area suitable for recharge (Sq. Km.)67.37 (42%)Lat. & Lon.12*20' 36" to 12* 31' 09" & 78* 00' 51" to 78* 09' 42".Rainfall897 mmMonsoon728 mmNon- Mon soon169 mmGeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and Migmattic complex Charnockite, granitic gneiss and Migmattic complexPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.GROUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & Longround water draft for domestic & Longround water draft0.916609 MCMIndustrial water supply143.5 %Uncommitted surface runoff available for total volume of weathered zone1283 MCMTotal volume of weathered zone1283 MCMTotal volume of weathered zone3Recharge shaft3Revizel, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted total groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge1.0554 MCMExcepted total groundwater recharge1.0554 MCMExcepted total groundwater recharge / saving1.96 m	AT A	GLANCE
Taluk Palacode District Dharmapuri State Tamil Nadu Total area (Sq. Km.) 160.41 Total area suitable for recharge (Sq. Km.) 67.37 (42%) Lat. & Lon. 12°20' 36" to 12° 31' 09" & 78° 00' 51" to 78° 09' Aurica 42°. Rainfall 897 mm Monsoon 728 mm Non-Mon soon 169 mm Geology Amphibolite / Pyroxene granulite, Basic rocks, Charnockte granitic gneiss and Migmatitic complex WATER LEVEL Pre - Monsoon Post - Monsoon 5 to 10 m bgl. Replenish able ground water resources 17.3472 MCM Net ground water available 15.6125 MCM Ground water draft for irrigation 21.496 MCM Ground water draft for irrigation 21.496 MCM Ground water draft 22.4126 MCM Industrial water supply 17.52 MCM Total volume of weathered zone 1283 MCM		
District Dharmapuri State Tamil Nadu Total area (Sq. Km.) 160.41 Total area suitable for recharge (Sq. Km.) 67.37 (42%) Lat. & Lon. 12*20' 36" to 12* 31' 09" & 78° 00' 51" to 78* 09' Rainfall 897 mm Monsoon 728 mm Non-Mon soon 169 mm Geology Amphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and Migmatitic complex WATER LEVEL Pre - Monsoon Pre - Monsoon 10 to 20 m bgl. Oround water available 15.6125 MCM Ground water resources 17.3472 MCM Net ground water available 15.6125 MCM Ground water draft for irrigation 21.496 MCM Ground water draft 22.4126 MCM Stage of ground water development (%) 143.5 % Uncommitted surface runoff available for 17.52 MCM Total volume of weathered zone 1283 MCM Total volume available for recharge 802 MCM (considering 3 m depth from 3 m bgl 3 ARTIFICIAL RECHARGE / CONSERVATION MEASURES 3 Structures Proposed (tentative) 3 Masonr		
State Tamil Nadu Total area (Sq. Km.) 160.41 Total area suitable for recharge (Sq. Km.) 67.37 (42%) Lat. & Lon. 12*20' 36" to 12* 31' 09" & 78° 00' 51" to 78° 09' Aurian 897 mm Monsoon 728 mm Non-Mon soon 169 mm Geology Amphibolite / Pyroxene granulite, Basic rocks, Charnockte, granitic gneiss and Migmatitic complex WATER LEVEL Pre - Monsoon 10 to 20 m bgl. Post - Monsoon Sto 10 m bgl. OROUND WATER RESOURCES ESTIMATION Replenish able ground water resources 17.3472 MCM Net ground water araft for irrigation CROUND WATER RESOURCES ESTIMATION Replenish able ground water resources 17.3472 MCM Net ground water araft for domestic & 0.916609 MCM 0.916609 MCM industrial water supply 143.5 % Uncommitted surface runoff available for 17.52 MCM Total yolume of weathered zone 1283 MCM Total volume of weathered zone Total volume of we		
Total area (Sq. Km.)160.41Total area suitable for recharge (Sq. Km.)67.37 (42%)Lat. & Lon.12°20'36" to 12° 31' 09" & 78° 00' 51" to 78° 09'42°.Rainfall897 mmMonsoon728 mmNon- Mon soon169 mmGeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and Migmatitic complexWATER LEVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.GROUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMNet ground water draft for domestic & industrial water supply0.916609 MCMTotal orund water draft22.4126 MCMStage of ground water draft22.4126 MCMStage of ground water draft143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMStructures Proposed (tenative) Masonry Check dam9Percolation pond Revinal, repair of pond, tanks with recharge shaft3Revinal, repair of pond, tanks with recharge shaft0.7 MCMExcepted groundwater recharge shaft1.0554 MCMExcepted groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge shaft1.956 MCMExcepted total groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge saving1.96 m		
Total area suitable for recharge (Sq. Km.)67.37 (42%)Lat. & Lon.12°20' 36" to 12° 31' 09" & 78° 00' 51" to 78° 09' 42".Rainfall897 mmMonsoon728 mmNon-Mon soon169 mmGeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and Migmatitic complexWATER LEVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.GROUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & lidustrial water supply0.916609 MCMTotal ground water development (%)143.5 %Uncommitted surface runoff available for recharge (considering 3 m depth from 3 m bgl7.52 MCMStructures Proposed (tentative) Masonry Check dam9Percolation pond Recharge shaft3Recharge shaft3Recharge shaft3Recharge shaft3Excepted total groundwater recharge shaft0.7 MCMExcepted total groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge shaft1.7554 MCMExcepted total groundwater recharge shaft1.95 m		
Lat. & Lon.12°20' 36" to 12° 31' 09" & 78° 00' 51" to 78° 09' 42".Rainfall897 mmMonsoon728 mmNon- Mon soon169 mmGeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and Migmatitic complex Charnockite, granitic gneiss and Migmatitic complexWATERLEVELPre - Monsoon5 to 10 m bgl.Post - Monsoon5 to 10 m bgl.GROUND WATER KEVURCES ESTIMATIONReplenish able ground water resources17.3472 MCMMater available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & Orgound water draft for domestic & 0.916609 MCMIndustrial water supply143.5 %Total ground water development (%)143.5 %Uncommitted surface runoff available for the Firka7.52 MCMTotal volume of weathered zone1283 MCMStructures Proposed (tentative) Masonry Check dam9Percolation pond Recharge shaft3Recharge shaft3Recharge shaft3Recharge shaft6Improving Water Efficiency / Saving (Mico Saving0.7 MCMExcepted total groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMExcepted total groundwater recharge / Saving1.7554 MCMExcepted total groundwater recharge / Saving1.96 m		
Rainfail897 mmMonsoon728 mmNon- Mon soon169 mmGeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockte, granitic gneiss and Migmatitic complexWATER LEVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.Replenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water draft23.3 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bglARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond irrigation system for 100 ha)3Excepted groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge1.0554 MCMExcepted total groundwater recharge1.7554 MCMSaving-Tentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging		
Monsoon728 mmNon-Mon soon169 mmGeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and Migmatitic complexWATER LEVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.ReQUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water draft28.3 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond3Recharge shaft3Reviral, repair of pond, tanks with recharge shaft0.7 MCMImproving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted total groundwater recharge1.0554 MCMExcepted total groundwater recharge1.754 MCMSavingTentative total cost of the projectRs.4.02 CrExpected raise in water le		42".
Non-Mon soon169 mmGeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockte, granitic gneiss and Migmatitic complexWATER LEVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.GROUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume of weathered zone1283 MCMStructures Proposed (tentative) Masonry Check dam9Percolation pond Revival, repair of pond, tanks with recharge shaft0.7 MCMImproving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge furgition system for 100 ha)0.7 MCMExcepted total groundwater recharge / Saving1.0554 MCMExcepted total groundwater recharge / Saving1.96 m	Rainfall	897 mm
GeologyAmphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and Migmatitic complexWATER LEVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.Post - Monsoon5 to 10 m bgl.Replenish able ground water resources17.3472 MCMRet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMMasonry Check dam9Percolation pond regist and the recharge shaft3Recharge shaft ririgation system for 100 ha)0.7 MCMExcepted total groundwater recharge saving1.0554 MCMExcepted total groundwater recharge / saving1.754 MCMExcepted raise in water level by recharging / 1.96 m1.96 m	Monsoon	728 mm
Charnockite, granitic gneiss and Migmatitic complexWATER REVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.Post - Monsoon5 to 10 m bgl.Replenish able ground water resources17.3472 MCCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMStructures Proposed (tentative) Masonry Check dam9Percolation pond Recharge shaft3Revival, repair of pond, tanks with recharge shaft0.7 MCMImproving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge sharing1.0554 MCMExcepted total groundwater recharge1.0554 MCMExcepted total groundwater recharge sharing1.96 m	Non- Mon soon	169 mm
WATER LEVELPre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.Replenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for odomestic &0.916609 MCMindustrial water supply143.5 %Total ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMStructures Proposed (tentative) Masonry Check dam9Percolation pond recitarge shaft3Recharge shaft3Revival, repair of pond, tanks with recharge shaft0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted groundwater recharge1.0554 MCMExcepted groundwater recharge1.0554 MCMExcepted total ground	Geology	Amphibolite / Pyroxene granulite, Basic rocks,
Pre - Monsoon10 to 20 m bgl.Post - Monsoon5 to 10 m bgl.GROUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water drevelopment (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMStructures Proposed (tentative) Masonry Check dam9Percolation pond sensifi3Recharge shaft3Revival, repair of pond, tanks with recharge shaft0.77 MCMExcepted groundwater recharge trigation system for 100 ha)1.0554 MCMExcepted total groundwater recharge favaing1.0554 MCMExcepted total groundwater recharge sharing1.0554 MCMExcepted total groundwater recharge favaing1.96 m		
Post - Monsoon5 to 10 m bgl.GROUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond irrigation system for 100 ha)3Excepted groundwater recharge shaft0.7 MCMExcepted groundwater recharge target in water level by recharge / 1.7554 MCM1.7554 MCMExcepted raise in water level by recharging / 1.96 m1.96 m	WAT	ER LEVEL
GROUND WATER RESOURCES ESTIMATIONReplenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGround water draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMStructures Proposed (tentative) Masonry Check dam9Percolation pond ringation system for 100 ha)3Excepted groundwater recharge shaft0.7 MCMExcepted groundwater recharge shaft1.0554 MCMExcepted groundwater recharge tructures total groundwater recharge1.754 MCMExcepted agroundwater recharge shaft1.754 MCMExcepted raise in water level by recharging / 1.96 m1.96 m	Pre - Monsoon	-
Replenish able ground water resources17.3472 MCMNet ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGroundwater draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMStructures Proposed (tentative) Masonry Check dam Percolation pond shftRecharge shaft shft3Revival, repair of pond, tanks with recharge shft0.7 MCMExcepted groundwater recharge strugt0.7 MCMExcepted total groundwater recharge shaft1.0554 MCMExcepted total groundwater recharge sharing1.7554 MCMExcepted total groundwater recharge / Saving1.796 m	Post - Monsoon	5 to 10 m bgl.
Net ground water available15.6125 MCMGround water draft for irrigation21.496 MCMGroundwater draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted total groundwater recharge saving1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMExcepted raise in water level by recharging / 1.96 m1.96 m	GROUND WATER R	ESOURCES ESTIMATION
Ground water draft for irrigation21.496 MCMGroundwater draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMCONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted total groundwater recharge saving1.0554 MCMExcepted total groundwater recharge saving1.7524 MCMExcepted rotal cost of the projectRs. 4.02 CrExpected raise in water level by recharging / 1.96 m1.96 m	Replenish able ground water resources	17.3472 MCM
Groundwater draft for domestic & industrial water supply0.916609 MCMTotal ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted total groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMFentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging / 1.96 m1.96 m	Net ground water available	15.6125 MCM
industrial water supplyIndustrial water supplyTotal ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMStructures Proposed (tentative) Masonry Check damPercolation pond Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted total groundwater recharge saving1.0554 MCMExcepted total groundwater recharge saving1.7554 MCMExcepted total groundwater recharge saving1.96 m	Ground water draft for irrigation	21.496 MCM
Total ground water draft22.4126 MCMStage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted total saving1.0554 MCMExcepted total groundwater recharge1.7554 MCMExcepted total saving1.7554 MCMExcepted rotal cost of the projectRs. 4.02 CrExpected raise in water level by recharging / 1.96 m1.96 m	Groundwater draft for domestic &	0.916609 MCM
Stage of ground water development (%)143.5 %Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCM ARTIFICIAL RECHARGE / CONSERVATION MEASURES Structures Proposed (tentative) Masonry Check damPercolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMFentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging / 1.96 m1.96 m	industrial water supply	
Uncommitted surface runoff available for the Firka17.52 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMExcepted total cost of the projectRs. 4.02 CrExpected raise in water level by recharging / 1.96 m1.96 m	Total ground water draft	22.4126 MCM
the Firka1283 MCMTotal volume of weathered zone1283 MCMTotal volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check damMasonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	Stage of ground water development (%)	143.5 %
Total volume available for recharge (considering 3 m depth from 3 m bgl802 MCMARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative) Masonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge1.7554 MCMExcepted total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m		17.52 MCM
(considering 3 m depth from 3 m bglARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative)9Masonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	Total volume of weathered zone	1283 MCM
(considering 3 m depth from 3 m bglARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative)9Masonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	Total volume available for recharge	802 MCM
ARTIFICIAL RECHARGE / CONSERVATION MEASURESStructures Proposed (tentative)9Masonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m		
Masonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m		CONSERVATION MEASURES
Masonry Check dam9Percolation pond3Recharge shaft3Revival, repair of pond, tanks with recharge6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	Structures Proposed (tentative)	
Recharge shaft3Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m		9
Revival, repair of pond, tanks with recharge shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	Percolation pond	3
shaft6Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	Recharge shaft	3
Improving Water Efficiency / Saving (Micro irrigation system for 100 ha)0.7 MCMExcepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	_	
irrigation system for 100 ha)Intersection is a system for 100 ha)Excepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	shaft	6
Excepted groundwater recharge1.0554 MCMExcepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging / I.96 m1.96 m	Improving Water Efficiency / Saving (Micro	0.7 MCM
Excepted total groundwater recharge / Saving1.7554 MCMTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging / 1.96 m1.96 m	irrigation system for 100 ha)	
SavingTentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m	Excepted groundwater recharge	1.0554 MCM
Tentative total cost of the projectRs. 4.02 CrExpected raise in water level by recharging /1.96 m		1.7554 MCM
Expected raise in water level by recharging / 1.96 m		Rs. 4.02 Cr

Plan on Artificial Recharge to Groundwater and Water Conservation in Vellichandai Firka, Palacode Taluk, Dharmapuri district, Tamil Nadu

1. Introduction

India is the largest user of groundwater in the world. Food grain security of the country is largely dependent on water resources and groundwater resources play major role in irrigation sector. Imprints of Over-Exploitation on groundwater resources are being observed as steep deepening of water levels, drying of shallow groundwater abstraction structures, ingress of salinity in fresh aquifers etc. which signal towards taking necessity of emergent action for artificial recharge and rainwater harvesting by utilizing surplus runoff and maintaining groundwater resources at sustainable stage.

In Tamil Nadu dependency on groundwater has increased many folds during the recent years and the groundwater extraction for irrigation, domestic and industries have resulted in lowering of water levels, long-term water level declining trend and even drying up of wells. In order to regulate the groundwater development, Central Ground Water Board in association with State Ground Water Departments has computed Dynamic Groundwater Resources and categorized firka as Over Exploited, Critical, Semi Critical and Safe.

Out of 1129 firkas (assessment units) in Tamil Nadu the groundwater situation in 374 firkas over-exploited, 48 firkas critical, 235 firkas semi-critical, 437 firkas safe and 35 firkas are saline. Various measures such as rainwater harvesting, artificial recharge and water use efficiency are successfully practiced by some NGOs, Central and State Govts., which need replication at larger scale in close coordination with State govt. agencies and stakeholders so that capacity building of state implementing agencies and awareness of stakeholders towards artificial recharge and rainwater harvesting can be made.

2. Objectives of the scheme

Objectives of the proposed scheme are

- To upscale recharge activities, supplement additional groundwater resources by harvesting surplus runoff, sustainability of groundwater resources at shallow depths
- Recovery of over-exploited groundwater areas by implementing artificial recharge measures in groundwater stress areas.
- Conservation, development and sustainable management of natural resources including their use.

3. Study area details

3.1 Location

The total area of Vellichandai firka is 160.41 sq.km and Vellichandai firka lies between North latitudes 12° 20' 36 "to 12° 31' 09" and east longitudes 78° 00' 51" to 78° 09' 42". Location map of Vellichandai firka is given in Figure 1.




Figure 1. Location map of Vellichandai firka

3.2 Geomorphological Set up

Geomorphologically, the area consists of hills and plain landforms. In plain landforms, Pediplain weathered moderate and shallow are occupied major part of the firka. These landforms are influencing the ground water recharge. Hill landform like residual hills, denudation hill and structural hills are act as runoff zone. (*Source: IRS, Anna University, Chennai Tamil Nadu)*. *Geomorphological map prepared using IRS- 1D data on 1: 50,000 scale and units are as per NNRMS standard*s. The various geomorphological units with its % of coverage area are given in Table 1. and shown in Figure 2.

LANDFORMS	% of Area
Denudational Hills / Residual Hills	2.17
Dissected/Undissected	10.31
Moderate	0.73
Pediment-Inselberg Complex	0.92
Shallow	26.53
Upland	59.35

Table 1. Various geomorphological units with its % of coverage area in Vellichandai firka




Figure 2. Geomorphology of Vellichandai Firka

3.3 Land use and soil

The land use pattern of the **Vellichandai** Firka is given in Figure 3. Predominantly the most of the area is characterised by the wet crop, plantation and dry crop (i.e., agricultural field) and accounts for 50 % of the total area of the firka (<u>Source: IRS, Anna University, Chennai Tamil Nadu</u>). This area is highly suitable for water conservation and recharge. The entire Firka is occupied by rock outcrops with loamy soil.




Figure 3. Landuse map of Vellichandai Firka

3.4 Drainage

The drainage pattern is the dendritic and sub- dendritic. The drainage map of Vellichandai firka is given in Figure 4.




Figure 4. Drainage map of Vellichandai Firka

3.5 Rainfall

Vellichandai area falls under tropical climate with temperature in the summer months of March to May. The average temperature varies from 26 to 41° C. The humidity is also high in the order of 80%. The wind speed is high during the months of July and August. The wind speed ranges from 7.4 to 12.6 km/hr, which increases from 100 to 120 km/hr during cyclone period.

Vellichandai Firka receives rainfall from southwest monsoon (June – September), northeast monsoon (October – December) and non-monsoon periods (January – May). The area receives the major rainfall from northeast monsoon. Rainfall is generally heavy during low-pressure depressions and cyclones during the northeast monsoon period. The normal annual rainfall is 897 mm.

Taluk	Name of Firka	Area in sq.km	Monsoon rainfall (Jun to Dec) In m	Non monsoon rainfall (Jan – May) In m	Total Rainfall In m
Palacode	Vellichandai	160.41	0.728	0.169	0.897

3.6 Hydrogeology

The entire firka is underlain by the crystalline metamorphic gneiss complex consisting Amphibolite / Pyroxene granulite, Basic rocks, Charnockite, granitic gneiss and migmatitic complex. Ground water is occurring in pheratic conditions in weathered and fractured gneiss rock formation. The weathering is highly erratic and the depth of abstraction structures is controlled by the intensity of weathering and fracturing. Large diameter dug well is more common ground water abstraction structures in the area. The diameter of the dug well is in the range of 7 to 10 m and depth of dug wells range from 15 to 18 m bgl. The dug wells yield up to 1 lps in summer months and few wells remains dry. The yield is adequate for irrigation for one or two crops in monsoon period.

The depth of wells varies from 6.64 to 17 m bgl. The hydrogeological map of Vellichandai firka is given in Figure 5.Decadal mean water level of pre-monsoon and post monsoon are given in Figures 6 a & b. The decadal maps reveal that, mean water level during pre-monsoon in majority area is < 5 m bgl likewise during post monsoon majority part is under < 5m ground water level. . The present water level in the firka is in the range of 10 to 20 mbgl (May).




Figure 5. Hydrogeological Map of Vellichandai Firka




Figure 6a. Decadal Pre -monsoon water level in Vellichandai firka




Figure 6 b. Decadal Post-monsoon water level in Vellichandai firka

3.7 Dynamic Ground water Resources

The ground water resources have been computed jointly by Central Ground Water Board and State Ground Water Resources Data Centre (PWD, WRO, Govt. of Tamil Nadu) as on 31st March 2011. The computation has been done using GEC1997 methodology. The salient features of the computations are furnished in Table 2.

Firka	GW WORTHY AREA	REPLENISH ABLE GROUND WATER RESOURCES	NET GROUND WATER AVAILABLE	GROUND WATER DRAFT FOR IRRIGATION	GROUNDWAT ER DRAFT FOR DOMESTIC & INDUSTRIAL WATER SUPPLY	TOTAL GROUN D WATER DRAFT	STAGE OF GROUND WATER DEVELOPM ENT (%)	CATEGORY
	(Sq. Km)		(MCM)					
Vellich andai	160.41	1734.72	15.6125	21.496	0.9166	22.412	143.5	OVER EXPLOITED

Table 2. Dynamic Ground water resources estimation of Vellichandai fir
--

4. Spatial Data Integration

The potential area for groundwater recharge is highly influenced by Geology, Geomorphology, Land use /land cover, Drainage, Surface Water Body, Weathered Thickness and first fractured Depth in the area. In order to ascertain the suitable area for groundwater recharge in firka, spatial data integration of have been attempted using index overlay model in GIS environ. In this model, seven layers have been integrated by assigning weightage for the theme having scale of 1-100 and sub-classes of the theme between 1 to 10 scales. The resultant map has been reclassified into four classes (High-low integrated values) indicating the suitable area for artificial recharge and given in Figure-7 and described below.

ZONE	% OF AREA COVERAGE	SIGNIFICANCE [*]
Very high	2	Suitable for all major recharge
		structures like Percolation pond
		and stop dam, check dam etc.,
High	17	Suitable for all major recharge
		structures like stop dam, check
		dam etc.,
Moderate	23	Suitable for all major recharge
		structures like earthen check
		dam, Boulder check dam and
		Nala bund etc.,
Poor	58	Hilly/Forest /Catchment area

^{*}However, the filed verification is required to confirm above potential area for groundwater recharge.




Figure 7 showing recharge worthy area

5. Planning for groundwater recharge /conservation

5.1 Justification of the artificial recharge & conservation measures

- The Firka is with high stage of groundwater development i.e.,143.6 % and with sufficient amount of uncommitted surface runoff/flow of 17.52 MCM.
- The total weathered zone available beneath the ground in the firka is 1283 MCM. Out of these total volume available for recharge considering 5m depth is 802 MCM.
- The Firka consists of sufficient numbers of surface water bodies /lakes which are well connected by the drainage. Revival and Recharge of these ponds will enhance the sustainability of the ground water abstraction structures.
- However, most of the ground water developments for agricultural purposes are met through dug-cum bore well and bore wells only. Hence, there is sufficient scope of recharge.
- Model generated in the areas reveals that more than 42 % of areas are suitable for recharge.
- In firka about 50 % areas is characterised by the agricultural activities, there is sufficient scope for the water conservation measures for enhance the crop production and better ground water development.

5.2 Availability of surplus surface water for artificial recharge or conservation

The uncommitted surface flow for Firka is estimated as per the norms followed by State Ground & Surface Water Resources data centre, PWD, Taramani, Chennai (Aug 2015). The available of surplus surface water for Firka is 17.52 MCM.

5.3 Proposed interventions including tentative location of artificial recharge /conservation measures

On basis of above description the following three type of approach have been made to propose artificial recharge or conservation structures.

- a. Artificial recharge
- b. Water conservation measure
- c. Water Efficiency

5.3.1 Artificial recharge

The details of artificial recharge structure proposed along with justification are given below.

5.3.1.1 Check dam

The seasonal drains in the firka carry heavy discharge during monsoon period. It is proposed that such seasonal streams / rivers will be identified and harnessed its seasonal water through construction of series of check dams. This will help in recharge to groundwater by increasing contact period between surface water and groundwater.

As per the integrated model prediction around 42 % of the firkas areas are suitable for these structures. It is proposed to construct 9 Check dams. The tentative location of these 9 ARs are given below and shown in Plate 1. The size and location of these structures are finalised after detailed field survey.

S. No.	Longitude	Latitude	Structures	
1	78.05	12.43	Check Dam	
2	78.06	12.42	Check Dam	
3	78.06	12.40	Check Dam	
4	78.04	12.42	Check Dam	
5	78.09	12.38	Check Dam	
6	78.08	12.37	Check Dam	
7	78.15	12.37	Check Dam	
8	78.09	12.36	Check Dam	
9	78.09	12.36	Check Dam	

Tentative location of proposed 9 Check dam in the firka

5.3.1.2 Recharge shaft

A recharge shaft has been proposed to facilitate the groundwater recharge in the surface water body. It has been proposed in the reservoir of the proposed revival pond and percolation pond in the firka. A total of 6 recharge shaft has been proposed in this firka. The tentative locations of recharge shaft are given in the map and presented in the given table.

5.3.1.3. Revival, repair of water bodies

The village tanks and ponds are source for the groundwater recharge. Several such villages ponds/ tanks are in dilapidated condition. These existing village tanks which are normally silted and damaged can be modified to serve as recharge structure in case these are suitably located to serve as percolation tanks. Through de-silting, coupled with providing proper waste weir, the village tanks can be converted into recharge structure. The locations of about 6 existing ponds/tanks have been identified with latitude and longitude given below and marked on Plate 1. Of 6, 3 tanks/ponds have been proposed to taken up for the renovation with recharge shaft. The remaining 3 tanks falling in the very high zone have been selected for the percolation tank with recharge shaft.

S	S. No.	LONGITUDE	LATITUDE	STRUCTURE	ACTION
	1	78.05	12.41	TANK / RESERVOIR	DE-SILTATION AND RECHARGE SHAFT

Tentative location of proposed de-siltation of pond/tanks with recharge shaft

S. No.	LONGITUDE	LATITUDE	STRUCTURE	ACTION
2	78.04	12.40	TANK / RESERVOIR	DE-SILTATION AND RECHARGE SHAFT
3	78.07	12.39	TANK / RESERVOIR	DE-SILTATION AND RECHARGE SHAFT

Tentative location of proposed Percolation pond/tanks with recharge shaft

S. No.	LONGITUDE	LATITUDE	STRUCTURE	ACTION
1	78.05	12.38	TANK / RESERVOIR	Percolation Tank with shaft
2	78.07	12.38	TANK / RESERVOIR	Percolation Tank with shaft
3	78.15	12.36	TANK / RESERVOIR	Percolation Tank with shaft

5.3.2 Water conservation measure


5.3.2.1 Farm Pond

A farm pond is a large dug out in the earth, usually square or rectangular in shape, which harvests rainwater and stores it for future use. It has an inlet to regulate inflow and an outlet to discharge excess water. The pond is surrounded by a small bund, which prevents erosion on the banks of the pond. The size and depth depend on the amount of land available, the type of soil, the farmer's water requirements, the cost of excavation, and the possible uses of the excavated earth. Water from the farm pond is conveyed to the fields manually, by pumping, or by both methods.

Advantages of Farm Ponds

- They provide water to start growing crops, without waiting for rain to fall.
- They provide irrigation water during dry spells between rainfalls. This increases the yield, the number of crops in one year, and the diversity of crops that can be grown.
- Bunds can be used to raise vegetables and fruit trees, thus supplying the farm household with an additional source of income and of nutritious food.
- Farmers are able to apply adequate farm inputs and perform farming operations at the appropriate time, thus increasing their productivity and their confidence in farming.
- They check soil erosion and minimize siltation of waterways and reservoirs.
- They supplies water for domestic purposes and livestock
- They promote fish rearing.
- They recharge the ground water.
- They improve drainage.
- The excavated earth has a very high value and can be used to enrich soil in the fields, levelling land, and constructing farm roads

As per the Landuse classification of the firka, majority of the area is covered by the agricultural field. Hence it is proposed to construct 100 farm ponds as per the specification of AED, Govt. of Tamil Nadu.



5.3.2.2. Micro Irrigation System (Sprinkler/ drip/ HDPE pipes)

Micro irrigation is defined as the frequent application of small quantities of water directly above and below the soil surface; usually as discrete drops, continuous drops or tiny streams through emitters placed along a water delivery line

In flood/furrow irrigation method more than 50% of applied water is wasted through seepage to deeper level, localized inundation causes loss through evaporation and it leaches out the nutrients from the plant. While through drip & sprinkler irrigation wastage of irrigational water could be minimized. The studies on different crops, has revealed that irrigation water is saved drastically. The conveyance losses (mainly seepage & evaporation) can be saved up to 25 to 40% through utilization of HDPE pipes. Initially the scheme is proposed to be implemented in worst affected areas showing deepest water levels and significant declining trends.

It is proposed to take up micro irrigation system in 100 ha. The cost estimation for this component has been taken from SOR of Agricultural Engineering Department (AED), Govt. of Tamil Nadu. Tentative locations of proposed micro irrigation are shown in Plate 1.




Plate - 1 Location map showing the proposed AR Structures

6. Tentative Cost Estimation

A tentative number of feasible structures, its cost and expected annual groundwater recharge / water saving is given in the Table 7. The unit rates are as followed by the PWD, Govt. of Tamil Nadu (Sources: Schedule of rates, Govt. of Tamil Nadu 2015).

Feasible Artificial Recharge & Water Conservation structures/ activities	Tentative Design	Quantity (in nos. or area in sq. m)	Total volume (Cu.m)	Tentative unit cost (Rs. lakh)	Total tentative cost (Rs. lakh)	Expected Annual GW recharge / Saving (Cu. m)	
	Red	charge Struct	ures/ Activities				
Masonry Check dams (5 Fillings)	Crest- 10 -15 m; Height- 1 – 1.5 m	9	153000	9	81	122400	
Percolation pond	150x150x1.5m	3	303750	25	75	243000	
Revival, repair of water bodies (3 Fillings)	(100mx100mx2.5m)	3		12	36		
Recharge shaft with the pond /tanks	Recharge shaft of 1.5 m dia. With 2m depth with filter media in lower 1 m Bore dia 10" Casing 6" Depth 30 m	6	225000	2	12	180000	
	V	Vater Conserv	vation Activities				
Farm Pond (in ha) (5 Fillings)	(30 m x 30m x 1.5 m)	100 Units	600000	1	100	510000	
Sprinkler/ drip/ HDPE pipes	For 1 ha with 5 m interval HDPE pipe	100 ha	100000	0.6 /ha	60	700000	
Subtotal - I		<u> </u>			364	1755400	
	Impact assessme	nt and O & N	И				
Piezometers Up to 5	Piezometers Up to 50 m bgl – 3 Nos. @ 0.6 lakh						
Subtotal - II	365.8						
O & M - 5 % of Subt	O & M - 5 % of Subtotal - II						
(Impact assessment	(Impact assessment to be carried out by the implementing agencies @ 5 % of Subtotal - II						
TENTATIVE TOTAL C	COST OF THE PROJECT				402.38		

Note:

> The type, number and cost of structure may vary according to site, after the ground truth verification

CD, PC – the storage of Check Dams and Percolation Ponds is also proposed for irrigating surrounding areas for enhancing groundwater recharge as well as effective utilization of the artificial recharge structures.

7. Implication modalities

The implementation of the scheme will be done by the line department of the state selected by the respective State authority. Further, it is to add that more than 50 % MGNREGA works related to water conservation/sustainable management, accordingly a convergence guideline has been made between National Rural Employment Guarantee Act (NREGA) (Ministry of Rural Development) & Programmes of Water Resources (MoWR, RD & GR). The district Dharamapuri is one among the list of districts identified for Convergence between NREGS and schemes of MoWR. The details of permissible works under convergence are envisaged in the Joint Convergence Guideline.

a.) Time schedule

Steps	1 st Quarter	2th Quarter	3 rd Quarter	4 th Quarter	5 th Quarter	6 th Quarter	7 th Quarter	8 th Quarter
 Identification of line department /implementing agency and preparation of DPR 								
 Approval of scheme and release of sanction of funds 								
 Implementation of ARS 								

Phase = one quarter or 3 months or equivalent to financial quarter

b.) Operation and maintenance

In all projects Impact assessment has to be carried out to ensure that projects is economically viable, socially equitable and environmentally sustainable by inter-related socioeconomic, cultural and human-health impacts, both beneficial and adverse. Accordingly it is proposed to have impact assessment at rate of 5 % of the total cost of the project for 5 years from the completion of artificial recharge.